



QUALITY CONTROL LABORATORY CORDITE FACTORY, ARUVANKADU TEST REPORT

No:21/TR/QC(LAB)/GL/ACETONE/05/25-26
Date:23/08/2025

NOMENCLATURE	: ACETONE
CONDITION OF THE SAMPLE	: GOOD
REFERENCE NUMBER	: QC S&P (MI) 25MI321
REFERENCE DATE	: 09/08/2025
SPECIFICATION	: IS:170 - 2020 (REV V)
LAB ITEM NO	: GL-1057/25-26
LAB ITEM NO DATE	: 09/08/2025
DATE OF PERFORMANCE OF THE TEST FROM	: 09/08/2025
DATE OF PERFORMANCE OF THE TEST TO	: 23/08/2025

Sl. No	TEST CLAUSE		RESULTS	SPECIFICATION LIMIT	TEST METHOD
1	DESCRIPTION		PASSES	The material shall be clear and free from any suspended matter	PARA 3.1
2	MISCIBILITY WITH WATER		PASSES	Shall show no turbidity on mixing with distilled water in any proportion at 27 ± 2 °C as verified visually.	PARA 3.2
3	PURITY, % BY MASS.		FACILITY NOT AVAILABLE	99.70 Min.	ANNEX -A
4	COLOUR, Pt-Co SCALE		<5	10 HAZEN UNIT Max.	IS 8768
5	RELATIVE DENSITY AT 27/27 °C		0.784	0.784 - 0.786	6 OF IS 82
6	DISTILLATION RANGE	INITIAL BOILING POINT	55.8	The difference between initial boiling point (IBP) and drypoint (DP) shall not exceed1°C including56.1°C (Temperature being corrected for a pressure of 760 mm Hg)	IS 1448 (PART - 18) METHOD B
		DRY POINT	56.3	The difference between initial boiling point (IBP) and drypoint (DP) shall not exceed1°C including56.1°C (Temperature being corrected for a pressure of 760 mm Hg)	IS 1448 (PART - 18) METHOD - B
7	WATER CONTENT, % BY MASS		0.4	0.4 Max.	IS 2362
8	RESIDUE ON EVAPORATION , mg /100 ml		1	5 Max.	8 OF IS 82
9	ACIDITY (AS CH3COOH) , g/100 mL		0.001	0.002 Max.	ANNEX - C
10	ALKALINITY		PASSES	To pass the test	ANNEX - D
11	PERMANGANATE TEST, MINUTES		60	30 Min.	ANNEX - E
12	ALCOHOLIC IMPURITIES		PASSES	To pass the test	ANNEX- F
13	BENZENE CONTENT, mg/kg		FACILITY NOT AVAILABLE	2.0 Max.	ANNEX- A
14	METHANOL CONTENT , mg/kg		FACILITY NOT AVAILABLE	300 Max.	ANNEX-A

Note:

- Results reported related only to the item/sample tested
- Report shall not be reproduced except in full without prior written permission of Group Officer
- Specification are mentioned wherever applicable
- Tests are done in respect of clauses required by user/consignee.
- Column whichever is not applicable may be treated as canceled.
- Sample is not drawn by Quality Control Laboratory.

Remarks : TEST FACILITY NOT AVAILABLE FOR CLAUSE No:- 3, 13 & 14. CLAUSE No:- 6 IS OPTIONAL NOT MANDATORY.

DO/QC(S&P)

Digitally Approved By
MURUKESAN.P
DO/QC(LAB)

Digitally Verified By
GOPAL B.
OIC/QC(LAB)

Tested By : N.VINOTH KUMAR
Report Generated by : VINOTH KUMAR N
Sampled By : DEEPA KRISHNA